### Please click the link to www.PipeMedic.com for the details.



# Infrastructure Innovators Since 1994 QuakeWrap, Inc.

6840 S. Tucson Blvd., Tucson, AZ 85756 (520) 791-7000, FAX (520) 791-0600 Toll Free (866) QuakeWrap (782-5397) www.quakewrap.com

# PROJECT PROFILE

96.inch diameter PCCP circulation water piping rehabilitation with QuakeWrap®

#### **FRP system at Apache Station**

Repair System: QuakeWrap FRP technology applied to rehab large underground PCCP water piping

Owner: ARIZONA G&T COOPERATIVES, INC. APACHE GENERATING STATION

Contact: Nathen Hatch, Ph: 520-586-5509, email: nhatch@azgt.coop

FRP Installer: FRP Construction

Design and Materials: QuakeWrap, Inc.

Location: Cochise, Arizona

#### **Project Synopsis:**

- The large diameter prestressed concrete cylinder pipes (PCCP) at Arizona G&T's Apache Generating Station were inspected with the electromagnetic technology and three segments were identified as in immediate need of structural repair.
- QuakeWrap (design and materials) and FRP Construction (installation) team was selected for a design-build solution.
- QuakeWrap designed a fully-structural carbon fiber reinforced polymer (CFRP) liner system to retrofit (3) 20-foot sections of 96-inch PCCP.
- The design followed the AWWA C305 guidelines with a CFRP system that can take external (soil) pressure and 82 psi of internal (hydrostatic) pressure.
- Overall system is comprised of a tack coat (high-adhesion epoxy), seven layers of carbon fiber laminae (QW U27C and B41C), and a 20-mil top coat (epoxy).
- End terminations included QuakeWrap's dual fiberglass fabric (B2610G) and EPDM compression seal placed on top of the glass and carbon fiber layers per the AWWA C305 end termination detail.
- Installation was performed successfully by FRP Construction in less than two weeks using the wet layup method, accommodating the owner's desire to minimize downtime.



## Infrastructure Innovators Since 1994 QuakeWrap, Inc.

6840 S. Tucson Blvd., Tucson, AZ 85756 (520) 791-7000, FAX (520) 791-0600 Toll Free (866) QuakeWrap (782-5397) www.quakewrap.com

# **Project Photos**



CFRP layers being applied with extra tack coat along the seams.



Compression seal (Weko) at the end termination.



Complete CFRP liner prior to applying top coat.